

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-069-20-106 000

LEASE NAME Bluemer Ardery

WELL NUMBER 19-9

SPOT LOCATION C SE NE SE

SEC. 19 TWP. 26 SRGE. 29 (X) or (W)

COUNTY Gray

Date Well Completed 4/26/81

Plugging Commenced 5/1/85

Plugging Completed 5/3/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Gary-Williams Oil Producer, Inc.

ADDRESS 115 Inverness Drive East, Englewood, CO 80112-5116

PHONE # (303) 799-3800 OPERATORS LICENSE NO. 6975

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Morrow Depth to top 4978 bottom 5000 T.D. 5155

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content         | From | To   | Size   | Put in | Pulled out |
|-----------|-----------------|------|------|--------|--------|------------|
| Glorietta | Water           | 1120 | 1250 | 8-5/8" | 507'   | none       |
| Swope     | Oil, Gas, Water | 4478 | 4510 | 4-1/2" | 5150'  | 868'       |
| Morrow    | Oil, Gas        | 4978 | 5000 |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

CIBP at 4925' with 20' of cement

Pump 50 sacks of cement at 850'

Pump 40 sacks of cement at 550' to 450'

Put 10 sacks of cement at 40' to 0'

Cut off and cap 8-5/8" casing 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506, Liberal, KS 67901

STATE OF Colorado COUNTY OF Arapahoe STATE CORPORATION COMMISSION, ss.

Ray Hager (employee of operator) of (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ray Hager  
(Address) 115 Inverness Drive East Englewood, CO 80112-5116

SUBSCRIBED AND SWORN TO before me this 11 day of June, 1985

My Commission expires: October 25, 1988

Nancy E. McDonald  
Notary Public

Re: *Sam. Gray* oil production  
 19-7 Blumcr. - ARDrey  
 C-SE-NE-SE.  
 19-26S-29W.  
 Gray. County. KANSAS.

Spud: APRIL 11 1981

Rotary Complete: APRIL 26 1981

Contractor: *Simmons Drilling Co. Rig #41*

Tool Pusher:

RECEIVED  
 STATE CORPORATION COMMISSION

Surface Pipe: *8 7/8 @ 507.*

MAY 01 1985

Production Pipe: *1/2 @ \$150 w/100 ft*

CONSERVATION DIVISION  
 Wichita, Kansas

Drill Time:

Samples:

DST: *none*

Cores: *none*

Mud: *Pro Chem.*

Log: *Schlumberger.*

RECEIVED  
 STATE CORPORATION COMMISSION  
 DIL. CO.

(Geologist on location *3900'*)  
 (Mud up: *4400'*; Type *premix*)

Elevation: *L+S.*

MAR 27 1985  
 CONSERVATION DIVISION  
 Wichita, Kansas

Gas Detector: *Conc. tube.*

Elevations: 2770 RB DF 2760 GL

| <u>TOPS</u>                    | <u>LOG</u>         | <u>SAMPLE</u> |
|--------------------------------|--------------------|---------------|
| <u>Stone Corral.</u>           | <u>2664</u>        |               |
| <u>CHASE</u>                   | <u>2664 + 106</u>  |               |
| <u>Stotler.</u>                | <u>3510 - 740</u>  |               |
| <u>Heebner</u>                 | <u>4094 - 1324</u> |               |
| <u>LASSING</u>                 | <u>4183 - 1413</u> |               |
| <u><del>Stark</del> STARK</u>  | <u>4468 - 1698</u> |               |
| <u>Base KANSAS C. ty.</u>      | <u>4620 - 1850</u> |               |
| <u>MARMA TON</u>               | <u>4640 - 1870</u> |               |
| <u>Cherokee</u>                | <u>4760 - 1990</u> |               |
| <u>MISSISSIPPIAN St. Gen.</u>  | <u>4904 - 2134</u> |               |
| <u>MISSISSIPPIAN St. Louis</u> | <u>4961 - 2191</u> |               |
| <u>Porosity.</u>               | <u>4978 - 2208</u> |               |
| <u>RTD</u>                     | <u>5154</u>        |               |
| <u>LTD</u>                     | <u>5155</u>        |               |