


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Harper County. Sec. 7 Twp. 31S Rge. 9W (E) (W)
Location as "NE/CNWxSWx" or footage from lines SW SW NW
Lease Owner Sierra Petroleum Co., Inc.
Lease Name HUDSON Well No. 1
Office Address 420 W. Douglas Ave., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 8/22/57 19
Application for plugging filed 8/21/57 19
Application for plugging approved 8/21/57 19
Plugging commenced 8/22/57 19
Plugging completed 8/22/57 19
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rivas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5032 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	202'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud from 5032 up to 200'. Set bridge w/wood plug 1/3 sks hulls and 20 sks cement through drill pipe. Filled hole to 35' set bridge w/wood plug, 1/3 sks hulls and 10 sks cement to cellar 0. Job complete 4 a.m. 8/23/57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 420 W. Douglas Ave., Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker
(Address) _____

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1957

My commission expires 1-30-61

Margie Cooper

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 31 R 9W
BOOK PAGE 31 LINE 45

Sierra Petroleum Co., Inc.

HUDSON #1

SW SW NW Sec. 7-31S-9W
Harper County, Kansas

Total Depth: 5032'

Elev: 1749 KB

Comm: 8/1/57
Comp: 8/22/57

Casing:

Cement:

8 5/8" @ 202'

with 125 sacks cement

FORMATION	DEPTH
Red bed	500
Shale & shells	805
Anhydrite & shale	850
Shale & shells	1195
Salt	1420
Shale & Lime	2095
Lime	2360
Lime & shale	3466
Lime	3587
Shale & lime	3649
Sand	3733
Shale & lime	3836
Lime	4235
Lime & chert	4272
Lime	4311
Shale & Lime	4413
Lime	4453
Lime & shale	4509
Miss	4518
Chert	4570
Chert, Lime & shale	4585
Miss Lime	4629
Lime chert	4665
Miss lime	4677
Lime & shale	4710
Shale	4765
Shale, lime & chert	4800
Lime & chert	4864
Simpson	4856
Sand, lime & chert	4876
Shale & sand	4990
Arbuckle lime	5032
Tops: Mississippi	4496
Simpson	4856
Arbuckle	4992

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. T. Honaker

Subscribed and sworn to before me this 26th day of August, 1957.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

PLUGGING			
FILE	SEC	T	R
	1	31	9W
BOOK	PAGE	LINE	
	39	45	