

STATE OF KANSAS
STATE CORPORATION COMMISSION
60 Colorado Derby Building
Topeka, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-203-20115-0000

LEASE NAME Uhland B

WELL NUMBER 1

1650 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 36 TWP. 20 RGE. 35 (E) or (W)

COUNTY Wichita

Date Well Completed _____

Plugging Commenced 08-20-94

Plugging Completed 08-20-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main, Ste 801, Wichita, Ks. 67202

PHONE/(316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-20-94 (date)

By Steve Middleton, Dodge City (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	291.04	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud; 1st plug from 2275' to 2075' w/50 sx.; 2nd plug from 1200' to 880' w/80 sx.; 3rd plug from 600' to 440' w/40 sx.; 4th plug from 320 to 120' w/50 sx.; 5th plug from 40' to surface w/10 sx.; rathole 15 sx.; total 245 sx, 60/40 posmix, 6% gel, 1/2# floseal per sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Ste. 801, Wichita, Ks. 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Sedgwick, ss.

A.L. Abercrombie, Inc. (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) Jack K. Wharton STATE CORPORATION COMMISSION
Jack K. Wharton
(Address) 150 N. Main, Ste 801, Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 26 day of August, 1994



Sandra C. McCaig
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1994
8-29-94

EFFECTIVE DATE: 8-13-94

DISTRICT #

SEAT Yes No

State of Kansas

NOTICE OF INTENTION TO DRILL 203-20,115-20

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 8 10 94 month day year

Spot SW NW SE Sec 36 Twp 20 S. Rg 35 East West

OPERATOR: License # 5422 ABERCROMBIE DRILLING Name: 150 N. MAIN, STE 801 Address: WICHITA, KS 67202 City/State/Zip: JERRY LANGREHR Contact Person: 316-262-1841 Phone:

1650' feet from South / North line of Section 2310' feet from East / West line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side County: WICHITA UHLAND B Lease Name: WILDCAT Well # 1 Field Name:

CONTRACTOR: License # 30684 ABERCROMBIE RTD, INC. Name:

Is this a Prorated/Spaced Field? yes no Target Formation(s): MARMATON Nearest lease or unit boundary: 330'

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary OWD Disposal X Wildcat Cable Seismic: # of Holes Other

Ground Surface Elevation: feet MS Water well within one-quarter mile: yes no Public water supply well within one mile: yes no

If OWD: old well information as follows:

Depth to bottom of fresh water: 100' Depth to bottom of usable water: 1180' Surface Pipe by Alternate: 1 Length of Surface Pipe Planned to be set: (260) 200

Operator: Well Name: Comp. Date: Old Total Depth

Length of Conductor pipe required: 0 Projected Total Depth: 5100' Formation at Total Depth: MISSISSIPPI

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: N/A

Water Source for Drilling Operations: well farm pond X other DNR Permit #: WILL FILE

Bottom Hole Location: Exp. 2/8/95

Will Cores Be Taken? yes X no If yes, proposed zone: N/A 200' Alt. II Req.

AFFIDAVIT

Pusher Terry Manda SPUD DATE 8-13-94 INIT. NW LENGTH SURFACE PLANNED 280-8 1/2" RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 2 1/4 @ 29' CONDUCTOR ANHYDRITE T- B- 2220 ELEVATION TD 5050 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N SX Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2225 Ft. W/ 50 SX 1/2 Base Anyh. @ 1200 Ft. W/ 20 SX 1/2, 1/2 Plug @ 600 Ft. W/ 40 SX Bottom Surface @ 320 Ft. W/ 50 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/T SX WATER WELL SX (Irr. Well Pond Hauling X) TECHNICIAN DATE 8-13-94 TYPE OF CEMENT 60/40 6 1/2 1/4 Flashed STARTING TIME 9:00 (AM/PM) DATE 8-29-94 COMPLETION TIME 2:00 (AM/PM) DATE 8-29-94 CEMENT COMPANY Allied