


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Wichita County. Sec. 36 Twp. 20S Rge. 35W (W)
Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Leben Drilling, Inc. etal
Lease Name Lawrence Well No. 1
Office Address Box 486, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-1-67 19
Application for plugging filed 10-1-67 19
Application for plugging approved 10-1-67 19
Plugging commenced 10-1-67 19
Plugging completed 10-1-67 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5127 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	455'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, spotted 100 sks. 50-50 Posmix, 6% gel @ 990' through drill pipe, 20 sks. 50-50 Posmix, 6% gel @ 450' bridged off @ 40', 10 sks. cement, 2 sks. cement in rathole

RECEIVED
OCT 5 1967
10-5-67
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1967

My commission expires April 1, 1971
Ulanda Nichols
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Leben Drilling, Inc. etal
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: LAWRENCE #1
 LOCATION: C NE NW SECTION 36-20S-35W
 WICHITA COUNTY, KANSAS
 COMMENCED: 9-19-67
 COMPLETED: 10-1-67

0	260	Sand, Clay
260	550	Shale
550	1440	Blue Shale, Clay, Redbed
1440	1600	Shells, Shale
1600	2245	Shale
2245	2265	Anhydrite
2265	2680	Shale
2680	3060	Shale, Lime
3060	3320	Lime, Shale
3320	3394	Shale, Lime
3394	3535	Lime, Shale
3535	3905	Chalky Lime
3905	4070	Chalky Lime, Shale
4070	5127	Lime
	<u>5127</u>	<u>RTD - D. & A.</u>

RECEIVED
 OCT 5 1967
 CONSERVATION DIVISION
 WICHITA, KANSAS

8 5/8" used surface casing set @ 455' cemented with 350 sacks of Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lawrence #1 Well, located C NE NW of Section 36, Township 20 South, Range 35 West, Wichita County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 4th day of October, 1967.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971