

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-203-20,131-000

LEASE NAME Horton

WELL NUMBER 1

1980 Ft. from <sup>N</sup> 8 Section Line

1980 Ft. from <sup>W</sup> 8 Section Line

SEC. 32 TWP. 20S RGE. 35 (E) or (W)

COUNTY Wichita

Date Well Completed 01-15-98

Plugging Commenced 01-12-98

Plugging Completed 01-15-98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Abercrombie Drilling, Inc.

ADDRESS 150 N. Main, Suite #801, Wichita, KS 67202

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5422

Character of Well D/A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-12-98 (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	306.84'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from     feet to     feet each set. Fill with heavy mud. 1st plug from 2290'-2090' with 50 sks, 2nd plug from 1100'-780' with 80 sks, 3rd plug from 650'-490' with 40 sks, 4th plug from 340'-180' with 40 sks, 5th plug from 40'-0' with 10 sks, 15 sks in rat hole.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Steve Frank

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of February, 19 98

Robert K. Ammerman  
 Notary Public

My Commission Expires: 3-1-2000

2-27-98



FOR KCC USE:

EFFECTIVE DATE: 1-5-98

DISTRICT # 1  
SGA? Yes  No

State of Kansas  
NOTICE OF INTENTION TO DRILL

203-20,131-000

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 01/25/98  
month day year

OPERATOR: License # 5422  
Name: Abercrombie Drilling, Inc.  
Address: 150 N. Main, Suite #901  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jerry Langrehr  
Phone: (316)-262-1841

CONTRACTOR: License #: 30684  
Name: Abercrombie RTD, Inc.

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWMO ... Disposal  Wildcat ... Cable  
... Seismic; ... # of Holes ... Other

If OWMO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes  no  
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_  
Exp. 6/30/98

Spot SE NW Sec 32 Twp 20 S, Rg 35  East  West

1980 feet from South (North) line of Section  
1980 feet from East (West) line of Section

IS SECTION  REGULAR  IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Wichita  
Lease Name: Horton Well #: 1  
Field Name: WC

Is this a Prorated/Spaced Field? ... yes  no  
Target Formation(s): LKC/Marmaton/Mississipp  
Nearest lease or unit boundary: 660

Ground Surface Elevation: EST. 3188 feet MSL  
Water well within one-quarter mile: ... yes  no  
Public water supply well within one mile: ... yes  no

Depth to bottom of fresh water: 180  
Depth to bottom of usable water: 1100

Surface Pipe by Alternate: 1  2  
Length of Surface Pipe Planned to be set: 300  
Length of Conductor pipe required: \_\_\_\_\_

Projected Total Depth: 5100  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:

well ... farm pond  other

Will Cores Be Taken? ... yes  no  
If yes, proposed zone: \_\_\_\_\_  
200' Alt. II Req.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

316 793 2808

usher Tenz PUD DATE 1-6-98 INIT. SA

ENGTH SURFACE PLANNED 300'

RESERVE PIT STATUS- REMOVE FLUID LINED  
fter salt sect. bbls. when done bbls.

ATHOLED AHEAD? Y N SIZE HOLE  
JRFACE PIPE @ CONDUCTOR  
NHYDRITE T- 2274 B- 2289 ELEVATION 32009

D 5150 FORMATION MISSISSIPPI  
w 4575-75-105-90mg  
AN PIPE 858 @ 306 DV TOOL ALT II DONE  
SX Y N

- Arbuckle Plug @ Ft. W/ SX
- Hug./Council @ Ft. W/ SX
- 1 Anhydrite Base @ 2290 Ft. W/ 50 SX
- 2 1/2 Base Anyh. @ 1100 Ft. W/ 80 SX
- 3 1/2, 1/2 Plug @ 650 Ft. W/ 40 SX
- 4 Bottom Surface @ 340 Ft. W/ 40 SX
- 5 40' Plug @ 0-40 Ft. W/ 10 SX

T HOLE CIRC/W 15 SX MOUSE HOLE W/ NO SX  
TER WELL SX (Irr. Well Pond Hauling  
CHNICIAN SA DATE 1-12-98

PE OF CEMENT 60/40 6% 1/4 FS  
ARTING TIME 5:00 (AM/PM) DATE 1-15-98  
MPLETION TIME 9:45 (AM/PM) DATE 1-15-98  
MENT COMPANY Allied