


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County. Sec. 34 Twp. 16S Rge. 23W (E) (W)

Location as "NE/CNW/SW" or footage from lines. C NW NW
Lease Owner Imperial Oil Company
Lease Name Schreiber Well No. 1
Office Address 780 Fourth Natl. Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 4/23/63 19
Application for plugging filed 4/23/63 19
Application for plugging approved 4/23/63 19
Plugging commenced 4/23/63 19
Plugging completed 4/23/63 19
Reason for abandonment of well or producing formation
No commercial quantities of oil found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4501 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface casing 8-5/8" at	318'	not pulled			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 600' with 20 sacks cement

Set second plug at 300' with 15 sacks cement

Set top plug at a 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 1963
5-3-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Knasas, Knc.
Address Box 97, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
John Lehman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman
780 Fourth Natl. Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 1963

My commission expires July 5, 1966

Bette J. Silcott
Notary Public.

15.135 - 19667-0000

DRILLER'S LOG

Imperial Oil Company
780 Fourth National Building
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1963

SCHREIBER NO. 1
C NW NW Sec. 34-16S-23W
Ness County, Kansas

Total Depth: 4501'

Elevation: 2476 K.B.

Commenced: 4/9/63 Completed: 4/23/63

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 318' with 200 sacks cement


Figures indicate bottom of formations:

Tops:

Sand & Clay	317'	Anhydrite	1805 (4671)
Shale	950'	Heebner	3855 (-1379)
Shale & Sand	1315'	Toronto	3873 (-1397)
Dakota Sand	1515'	Lansing	3892 (-1416)
Shale & Red Bed	1805'	B/Kansas City	4174 (-1698)
Anhydrite	1839'	Fort Scott	4272 (-1796)
Shale & Shells	2440'	Cherokee Shale	4359 (-1883)
Shale & Lime	3436'	Warsaw	4455 (-1979)
Lime & Chalk	3740'	Osage	4466 (-1990)
Lime & Shale	3863'		
Lime	4070'		
Lime & Chert	4112'		
Lime	4501'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY


Raymond R. Dombaugh

Subscribed and sworn to before me this 30th day of April, 1963.

My Commission Expires:

July 5, 1966


Bette J. Silcott, Notary Public