

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,918-0000

LEASE NAME Mishler "L"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

330 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 32 TWP. 16 RGE. 23 (S or W)

COUNTY Ness

Date Well Completed 10-2-85

Plugging Commenced 1:30 PM

Plugging Completed 3:30 PM

LEASE OPERATOR Palomino Petroleum

ADDRESS P.O. Box 18610

PHONE# (316) 683-8152 OPERATORS LICENSE NO. 5161

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Dodge City

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation None Depth to Top _____ Bottom _____ T.D. 4570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface hole	Sand & Shale	0	248	8 5/8	241	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug @ 1855' - 50 sx, plug @ 950' - 80 sx, plug @ 500' - 40 sx, plug @ 250' - 40 sx, plug @ 40' - 10 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DNB Drilling, Inc. License No. 5476

Address 535 N. Oliver Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Bob Watchous (XXXXXXXXXXXXXXXXXXXX) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bob Watchous

(Address) Box 18610 Wichita, KS. 67218

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 85


Kathryn L. Frerking
Notary Public

My Commission Expires: August 21, 1989



OCT 21 1985
10-21-85
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84



D N B Drilling, Inc. 15135-22918-0000

ROTARY CONTRACTOR DRILLING DEALS

J. L. DONELSON, PRES.
(316) 687-5471

535 NORTH OLIVER

WICHITA, KANSAS 67208

DRILLERS' LOG

Palomino Petroleum
P.O. Box 18610
Wichita, KS 67218

#2 Mishler "L"
SE SW SW Sec. 32-16-23W
Ness County, Kansas

Commenced: 9-26-85
Completed: 10-2-85

Surface casing: Ran 6 jts. 8 5/8", 20# new casing. Tallied 240.72',
set @ 248'. Cemented with 200 sx 60/40 pozmix, 2%
gel, 3% cc. Cement did circulate.

FORMATION

Sand & Shale
Shale
Anhydrite
Shale
Shale & Lime
Lime

DEPTH

0-1550
1550-1822
1822-1855
1855-3355
3355-4030
4030-4570 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB Drilling, Inc.


By *J. L. Donelson*

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 9th day of October, 1985.

Vicky L. Coppage, Notary Public

My appointment expires:
May 28, 1989



Vicky L. Coppage
STATE CORPORATION COMMISSION

OCT 21 1985