


15.185.21315.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Ness County. Sec. 31 Twp. 16 Rge. (E) 23 (W)
Location as "NE/CN\KSW2" or footage from lines C SE SW
Lease Owner Walters Drilling Co., Inc.
Lease Name Klitzke 'B' Well No. 1
Office Address 400 Insurance Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/25/77 19
Application for plugging filed 4/25/77 19
Application for plugging approved 4/25/77 19
Plugging commenced 4/25/77 19
Plugging completed 4/25/77 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	302	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 720' with 70 sacks
Middle plug at 240' with 20 sacks
Top & bridge @ 40' with 10 sacks,
2 sacks in rathole
Job complete at 2:15 a.m. 4/25/77

RECEIVED
STATE CORPORATION COMMISSION
MAY 09 1977
5-9-77
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Company, Inc.
Address 408 One Twenty Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.
Jim Thatcher


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Thatcher
408 One Twenty Building, Wichita 67202
(Address)

Subscribed and Sworn to before me this 7 day of May 19 77

My commission expires January 17, 1981

Mary Lou Taylor
Notary Public.



DRILLERS LOG

OPERATOR: WALTERS DRILLING COMPANY
 400 Insurance Building
 Wichita, Kansas 67202

LEASE NAME: Klitzke 'B' No. 1
 C SE SW Sec. 31-16S-23W
 Ness County, Kansas

RTD: 4565'

CONTRACTOR: Slawson Drilling Company, Inc.
 408 One Twenty Building
 Wichita, Kansas 67202

COMMENCED: 4/16/77

COMPLETED: 4/25/77

CASING: New 8-5/8" set at 302' with 200 sacks cement

0' to 307' Surface clay & shale
 307' to 345' Shale
 345' to 1233' Shale & Sand
 1233' to 1275' Sand Streaks
 1275' to 1844' Sand & Shale & Shells
 1844' to 1895' Anhydrite
 1895' to 2645' Shale & Shells
 2645' to 4025' Lime & Shale
 4025' to 4470' Lime
 4470' to 4532' Lime & Shale
 4532' to 4542' Lime
 4542' to 4565' Mississippian
 RTD 4565'

RECEIVED
 STATE COMPLETION COMMISSION
 MAY 09 1977
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, Jim Thatcher, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is a true and correct copy of the log of the Klitzke 'B' No. 1 well.

Jim Thatcher
 JIM THATCHER

Subscribed and sworn to me this 7th day of May, 1977.

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1981

