

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Harper County, Sec. 4 Twp. 31S Rge. 8 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE SE NW

Lease Owner Mull Drilling Company, Inc.

Lease Name Culver Well No. A-2

Office Address 1625 Wichita Plaza Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 7-27-67 19

Application for plugging approved 7-28-67 19

Plugging commenced 8-2-67 19

Plugging completed 8-23-67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Archie V. Elving

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4503 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	195	None
				5 1/2	None	3106

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar.

Moved in. Rigged up unit.

Sanded to 4400'. Dumped 5 sacks of cement. Working pipe.

Working pipe. Shot pipe at 3800'. Pulling pipe.

Working pipe. Pipe stuck. Shot pipe at 2600'.

Working pipe. Shot pipe at 2500' - 2400' - 2300' - 2200' - 2100' - 2000' and 1920'. Pulling pipe.

Pulling pipe. Plugging well. Build rock bridge at 215'. Dumped 25 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks. Well completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of August, 1967.

My commission expires May 27, 1969

Notary Public.

RECEIVED
AUG 29 1967
CONSERVATION DIVISION
WICHITA, KANSAS

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 8/31/59

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 9/12/59

CASING RECORD: Set 195' 8 5/8" w/150 sax cmt.
Set 5 1/2" @ 4497'

LOCATION: CULVER "A" #2
NE SE NW 4-31S-0W
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

500'	Red Bed
735'	Shale
1300'	Shale & Shells
1830'	Shale & Lime
2075'	Lime
3148'	Lime & Shale
3650'	Sandy Lime & Shale
3861'	Lime w/Shale
4169'	Lime
4223'	Lime & Shale
4276'	Lime
4370'	Lime & Shale
4497'	Mississippi Chert - total depth

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1967
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

J. A. Mull, Jr.
J. A. Mull, Jr.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 16th day of September, 1959.

Walter H. Miller
Notary Public

My Commission Expires: February 24, 1960