

WELL PLUGGING RECORD

Give All Information Completely
Make Required Abbrev
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
520 State Building
Wichita, Kansas

HARPER

County. Sec. 4 Twp. 31 Rge. 9 (E) W (W)

Location as "NE/CNWSWK" or footage from lines NE-SE-NW

Lease Owner PETROLEUM, INCORPORATED

Lease Name FREELAND "B" Well No. 2

Office Address 311 East Third, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 21 1956

Application for plugging filed April 16 1956

Application for plugging approved April 18 1956

Plugging commenced May 4 1956

Plugging completed May 15 1956

Reason for abandonment of well or producing formation No Producing Zones

If a producing well is abandoned, date of last production ----- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4,544 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
MISSISSIPPI	Little Gas and Water	4428'	4442'	5 5/8" OD	216'	None
		4450'	4464'	4 1/2" OD	4542'	3818'
		4472'	4484'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(Plugged back to 4485')
Mudded up hole to 215' with heavy mud, built solid rock bridge at 215'. Placed 20 sacks cement on top of bridge and mudded up to 35'. Made solid rock bridge at 35', and filled hole to base of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Morgan Well Plugging Service
Address 102 West 18th Street, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (AGENT) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of MAY, 1956

Ray B. Anderson
Notary Public.

My commission expires NOVEMBER 21, 1957

PLUGGING
FILE SEC 4 T 31 R 9W
BOOK PAGE 54 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1956
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY **Petroleum, Inc.**

SEC. **4** T. **31S** R. **9W**

FARM **Freeland 'B'** NO. **2**


LOC. **NE SE NW**
1650' FNL
2310' FNL

TOTAL DEPTH **4544'**

COUNTY **Harper**

COMM. **January 15, 1956** COMP. **February 1, 1956**

CONTRACTOR **Carvey Drilling Company**



CASING **8-5/8" @ 216' w/150 sax**
4-1/2" @ 4542' w/100 sax

ELEVATION **1701 D7**
1703 RB

PRODUCTION **Mississippian**

FIGURES INDICATE BOTTOM OF FORMATIONS

140	Sand
216	Red Bed & Shale
1514	Shells & Shale
1775	Lime & Shale
2135	Lime
3034	Shale & Lime
3408	Lime
3555	Lime & Shale
3732	Sand & Lime
4209	Lime
4298	Shale & Lime
4410	Lime
4458	Lime & Chert
4530	Lime & Shale
4544	Lime
4544	RTD

Sample Tops

Heebner	3502	(-1799)
Toronto	3525	(-1822)
Base Oread	3545	(-1842)
Lansing	3711	(-2008)
Mississippi	4422	(-2719)
Miss. Lime	4498	(-2795)

PLUGGING

FILE SEC. 4 T. 31 R. 9W

BOOK PAGE 54 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1956
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of SEDGWICK } ss:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the FREELAND 'B' #2 well

Karl E. Becker

Subscribed and sworn to before me this 8th day of February 19 56

My Commission Expires: September 2, 1959

Frances Sloan
NOTARY PUBLIC

FRANCES SLOAN, Notary Public
My Commission expires Sept. 2, 1959