


15-077-20391-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Harper County. Sec. 6 Twp. 31S Rge. 9W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

NE SE
Lease Owner E. K. Edmiston
Lease Name Jacobs "C" Well No. 1
Office Address 800 Vickers KSB&T Bldg., Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole
Date Well completed December 19, 1976
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced December 19, 1976
Plugging completed December 19, 1976
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4535'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,535 ft. (rotary total depth) to 240 ft. Set plug at 240 ft. and cemented with 35 sacks cement.
Filled hole with heavy rotary mud from 240 ft. to 40 ft.
Set solid plug at 40 ft. and cemented to cellar with 15 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well Cementing pump truck through 4-1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this report.)
Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.

Dean Britting, Agent

~~XXXXXX~~ of owner ~~XXXXXX~~ of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting


200 No. Main, Wichita, Kansas 67202
(Address)

Subscribed and Sworn to before me this 22nd. day of December, 19 76

My commission expires June 30, 1978

Elsie Willison
Elsie Willison -

Notary Public.



KANSAS GEOLOGICAL SOCIETY API NO. - 15-077-20,391
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **E. K. Edmiston**

SEC. **6** T. **31S** R. **9W**
 LOC. **NE SE**

FARM **Jacobs "C"** NO. **1**

COUNTY **Harper**
 KANSAS


TOTAL DEPTH **4,535'**
 COMM. **December 9, 1976**

COMP. **December 19, 1976**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED **December 22, 1976**



CASING

20	10	
15		8-5/8" 245' cemented w/175 sxs cement
12		ELEVATION 1709 KB
13	5	

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	250'
Shale	485'
Red Bed	960'
Shale and Shells	1,490'
Lime and Shale	1,543'
Shale and Lime	1,632'
Lime and Shale	1,860'
Shale and Lime	2,040'
Lime and Shale	2,201'
Shale and Lime	3,210'
Lime	3,283'
Lime and Shale	3,430'
Shale and Lime	3,580'
Lime and Shale	3,910'
Shale and Lime	4,020'
Lime	4,268'
Lime and Shale	4,394'
Lime	4,535'
Rotary Total Depth	4,535'

RECEIVED
 STATE CORPORATION COMMISSION

DEC 23 1976

CONSERVATION DIVISION
 Wichita, Kansas


I hereby certify the above and foregoing
 to be a true and correct log of the above
 described well as shown by the drilling
 reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas }
 County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary
 Public in and for said county and state
 this 22nd. day of December, 1976.



Elsie Willison
 Elsie Willison - Notary Public

My Commission Expires:
 June 30, 1978