

15-077-20210-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

HARPER County, Sec. 11 Twp. 31S Rge. (E) 9 (W)

Location as "NE/CNW/SE" or footage from lines NW NW SE
Lease Owner BEREN CORPORATION
Lease Name MILLER DRAKE Well No. 1
Office Address 1130 Vickers-KSB&T Building, Wichita, Ks 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 10/18 19 73
Application for plugging filed 10/18 19 73
Application for plugging approved 10/18 19 73
Plugging commenced 10/18 19 73
Plugging completed 10/18 19 73
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well RUSSELL BIBERSTEIN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4425 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clay, sand & shale		0	250	8 5/8	250	0
		0	80	13 3/8	80	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug w/40 sks @ 240'
Fluid to 40' w/ 1/4 sk hulls, 10 sks cement
Complete @ 11 AM by Howco.

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GABBERT-JONES, INC. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack W. Gabbert
830 Sutton Place (Address)

26 day of October, 19 73



Nov. 29, 1973

Marjorie Hall
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 29 1973
 CONSERVATION DIVISION
 Wichita, Kansas

MILLER-DRAKE #1
 NW NW SE
 Section 11-31S-9W
 Harper County, Kansas

Commenced: October 4, 1973
 Completed: October 18, 1973

OPERATOR: BEREN CORPORATION

DEPTH		FORMATION	REMARKS
From	To		
0	250	Surface clay-sand-shale	Ran Ran 2 jts of new 13 3/8" csg 61# csg, L.D. @ 80' w/70 sks 60-40 Posmix, 2% Gel, 3% CC Complete @ 9:30 PM 10/4/1973
250	870	Redbed-shale	
870	1125	Shale-shells	
1125	1410	Shale-lime	
1410	2175	Lime-shale	
2175	2682	Shale	
2682	3680	Shale-lime	
3680	3720	Lime-shale	
3720	4425	Lime	
4425		TD	

DRY AND ABANDONED


I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NW SE, Section 11-31S-9W, Harper County, Kansas to the best of my knowledge and belief.

James S. Sutton, II
 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 24th day of October, 1973, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



Marjorie Hall
 Marjorie Hall