

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Harper County, Sec. 11 Twp. 31 Rge. 9 (W)

Location as "NE/CNW%SW%" or footage from lines C NW-SE

Lease Owner Barbara Oil Company

Lease Name Ryan-Drake Unit Well No. 1

Office Address 509 Union Center, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed June 17, 19 59

Application for plugging filed February 26, 19 71

Application for plugging approved March 1, 19 71

Plugging commenced March 20, 19 71

Plugging completed March 20, 19 71

Reason for abandonment of well or producing formation No longer economically feasible to produce.

If a producing well is abandoned, date of last production January 13, 19 71

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Mississippi Depth to top 4380 Bottom 4435 Total Depth of Well 4435 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7 5/8"	400'	-0-
				4 1/2"	4434'	2750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set Lane Wells Plug @ 3100'  
Gravel to 2862' W/ 4 sx. of cement on top.  
Mud to 300'  
Bridge @ 300' & cement to surface.

Plugging completed at 12:00 Noon on 3-20-71

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Oilfield Service  
Address P.O. Box 187, Medicine Lodge, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. Douglas Myers (employee of owner) or (owner or operator) of the above


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log book above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Douglas Myers  
509 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of March, 19 71

My commission expires August 12, 1971

Doris Oglesbee  
Doris Oglesbee  
Notary Public.



ROTARY DRILLING LOG

OPERATOR: The Texas Company  
 Ryan-Drake Unit #1  
 C NW SE Sec. 11-31-9W  
 Harper County, Kansas

CONTRACTOR: Capitt Drilling Inc.  
 COME: 6-4-59  
 COMP: 6-17-59

Formations:

Surface Clay	105'
Shale & Shells	125'
Lime & Shale	411'
Shale & Lime	780'
Shale	1100'
Shale & Lime Shells	1560'
Shale & Lime	1750'
Lime & Shale	1892'
Lime & Shale Strks.	2045'
Shale & Lime	2357'
Shale w/Lime Strks.	2660'
Lime & Shale	3690'
Lime	4167'
Lime & Shale	4376'
Lime	4435'
Rotary Total Depth	4435'

Remarks: Set 400' of 7 5/8" surface casing at 411' cemented with 325 sbs. NAC5 cement.

Set 4 1/2" casing at 4134' cemented with 75 sacks Foxmix with 1/4 of 1% Flo cele.

We certify the above log is true and correct to the best of our knowledge and belief.

CAPITT DRILLING, INC.

*R. R. McDaniel*  
 R. R. McDaniel