

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-21988-0000

LEASE NAME Baer

WELL NUMBER 4

 Ft. from S Section Line

50' W S/2 S/2 Ft. from E Section Line

SEC. 16 TWP. 16 RGE. 23 (E) or (W)

COUNTY Ness

Date Well Completed 2-88

Plugging Commenced 7-17-91

Plugging Completed 7-17-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# 913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-17-91 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4446

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

7-22-91

JUL 22 1991

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	339	8 5/8		None
	Casing	0	4445'	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Trip in opened to 1530'. Mix and spot 10 sk gel. Pull 2 jts. spot 25 sk. 60/40 pos. 6% gel. 3% CC. Pull tubing to 1030'. Circulate hole clean. Pull tubing. Tag cement at 1225'. OK.
 Perf. 2 holes at 1050'. Run tubing to 1080'. Mix 60 sk. 60/40 pos. 6% gel. Circulate to surface. Hook to 8 5/8 and pump in 110 sk. 60/40 pos. Hook to 4 1/2 casing and squeeze in 35 sk, 60/40 pos, 6% gel. Max. 700# 500 SIP
 (Additional description, if necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beren Corp.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

SUBSCRIBED AND SWORN TO before me this 18 day of July, 19 91

NOTARY PUBLIC - State of Kansas
 ROSEMARY SMITH
 My Appt. Exp. 5-1-1995

Rosemary Smith
 Notary Public

My Commission Expires: 5-1-1995