


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Ness County. Sec. 12 Twp. 16 Rge. 23 ~~021~~ (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW&SW&" or footage from lines NW NW NE  
Lease Owner Welch & Olsson Drilling Company, Inc.  
Lease Name Turner Well No. 1  
Office Address 203 Rule Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 7-9 19 55  
Application for plugging filed 7-9 19 55  
Application for plugging approved 7-9 19 55  
Plugging commenced 7-9 19 55  
Plugging completed 7-9 19 55  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner, Box 207, Great Bend, Ks.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4830' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	269.20"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 250'. Put in 1/3rd sack of hulls. Set plug and cemented with 20 sacks of cement through drill pipe.  
Filled hole with mud to 35'; added 1/3rd sack of hulls and set second plug and cemented with ten sacks of cement.  
Cemented to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
8-19-55  
AUG 19 1955

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Company, Inc.  
Address 203 Rule Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. E. Welch (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
203 Rule Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of July, 19 55

My commission expires June 12, 1959

Edith Erker Notary Public.

PLUGGING  
FILE SEC 12 T 16 R 23W  
BOOK PAGE 34 LINE 13

WELL LOG.

WELCH & OLSSON DRILLING COMPANY, INC.

Elevation: 2374 R. B.

CONTRACTOR: WELCH & OLSSON DRILLING CO. Inc.

Comm. Drlg: 6-25-55

TURNER #1

Compl. Drlg: 7-9-55

NW NW NE Sec. 12-16-23W

Ness County, Kansas.

Production: D & A.

Casing Record.

Set 269.20' of 8 5/8" with 200 sacks of cement.

(Figures indicated bottom of formations.)

<u>FORMATIONS</u>	<u>DEPTHS</u>	<u>FORMATION TOPS.</u>	
Surface soil:	115	Heebner:	3731 (-1357)
Sand & Shale:	263	Lansing-Kansas City:	3768 (-1394)
Shale:	650	Base Kansas City	4049 (-1675)
Sand:	760	Cherokee Shale:	4221 (-1847)
Shale & Redbed:	950	Mississippian:	4334 (-1960)
Sand:	1010	Viola:	4509 (-2135)
Red Bed:	1165	Arbuckle:	4730 (-2356)
Anhydrite:	1585		
Shale & Shells:	2360		
Shale & Lime:	2470		
Lime:	2485		
Lime & Shale:	2620		
Shale W.Lime Strs:	2710		
Shale & Lime:	2815		
Shale & Lime:	3035		
Shale & Shells:	3313		
Shale & Lime:	3445		
Lime:4330	4330		
Shale & Lime:	4340		
Chert:	4368		
Chert & Lime:	4453		
Lime & Chert:	4496		
Chert W/Lime:	4550		
Lime & Chert W/Shale:	4585		
Chert & Lime:	4645		
Chert:	4726		
Lime & Chert:	4777		
Chert:	4830 T.D.		

STATE OF KANSAS, )  
 ) SS:  
 SEDGWICK COUNTY, )

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 19 1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the NW NW NE of Section 12, Township 16, Range 23 W, Ness County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.

BY [Signature]  
 R. E. WELCH

Subscribed and sworn to before me this 18th day of July, 1955

[Signature]  
 Notary Public.

My commission expires:  
 June 12, 1959

PLUGGING  
 WELL SEC 12, 16, 23W  
 BOOK PAGE 134 UNIT 13