

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 27 Twp. 30 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SW NE

Lease Owner Tom Kat, Inc.

Lease Name Thom Well No. 1

Office Address 1127 Wichita Plaza

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 11/12 1966

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 11/12 1966

Plugging completed 11/12 1966

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Douglas Depth to top Bottom Total Depth of Well 3789 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	261.17'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled to 250' with heavy mud. Set plug

at 250', Howco Plug, 1 sack hulls, 1 sack dry cement,

put in 24 sacks cement. Filled hole to 40'. Set plug

at 40'. Put in 10 sacks cement. Filled-hole-to-40'.

Put 25 sacks cement in rathole.

Plugging complete 10:00 p.m.

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1967
01-05-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kansas COUNTY OF Sedgwick, ss.

William C. Stewart

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William C. Stewart

1127 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 66

April 16, 1969

Carolyn L. Scott
Notary Public.

My commission expires

15-007-30277-00-00

DRILLERS LOG

#1 THOM

BARBER COUNTY, KANSAS

Elevation: 1775 KB
Commenced: 11/6/66
Completed: 11/12/66

FROM	TO	
0	60	Sand
60	945	Red Bed & Shale
945	1720	Shale & Shells
1720	3511	Shale & Lime
3511	3575	Sand
3575	3750	Shale & Lime
3750	3773	Sand
3773	3789	Sand & Shale
3789		RTD

FORMATION TOPS:

Heebner shale	3671	(-1896)
Douglas Sand section	3748	(-1973)
Clean Douglas Sand	3756	(-1981)
Lower Douglas	3783	(-2008)
Rotary Total Depth	3789	(-2014)

REMARKS:

Set 261.17' of 8 5/8" surface casing with 210 sacks of cement.

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1967
01-05-1967
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 23rd day of _____

December, 1966.

My commission expires: April 16, 1969

Cyril L. Scott