

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1983

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

CONSERVATION DIVISION
Wichita, Kansas

COUNTY Harper SEC. 19 TWP. 325 RGE. 8 E/W
Location as in quarters or footage from lines:
C. - N.E. - N.W.

Lease Owner Resource Venture Corp.
Lease Name Ferrell Well No. 1
Office Address 1501 Superior/Lincoln, NB 68521
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 11/29/1981
Application for plugging filed 1/24/1983
Plugging commenced 1/26/1983
Plugging completed 2/7/1983 2:00 a.m.
Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M.V. Leslie / Glenn Ward
Producing formation _____ Depth to top _____ bottom T.D. 3787'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	300	none
				4 1/2	3762	3131

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____
feet to _____ feet for each plug set. Plugged back at 3762. Sand from 3762 to 3730.

4 sacks of cement with dump bailer 3730 to 3700. Ripped at 3300 and 3200.

3 hulls, 6 jell, 125 sacks of common, 3% c.c. I talked to Glen Ward for top.

plugged 2/4/1983 10:45 a.m. Elmo on location. Vangesean on location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corp.

STATE OF Kansas COUNTY OF Barber, ss.
Elmo Mergeste (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Elmo Mergeste
Mergeste & Sons Inc
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1983

Jessie Hamilton
Notary Public.

My Commission expires: April 4, 1986.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

STATE OF KANSAS
 JAN 24 1983
 County of Sedgwick
 Wichita

Farrell #1 O/W/O
 NE-SW Sec 24-32S-9W
 Harper County Kansas

Old Information:

OPERATOR: RESOURCES VENTURES CORP.

Commenced: 9-4-81
 Completed: 9-12-81
 TD: 3756

New Information:

OPERATOR: RESOURCES VENTURES CORP.

Commenced: 11-28-81
 Completed: 11-29-81
 TD: 3763

Lioret 3195

Depth From	to	Formation	Remarks
0	3763	Heavy Mud-Cement	<p>Ran 7 jts of 24# 8 5/8" csg 300' Cemented w/225 sks Common (Was: Resources Ventures Corp. #1 FEREEL)</p> <p>Ran 90 jts of 10 1/2# 4 1/2" csg set @ 3762' Cemented w/ 125 sks 60/40 Fosmix 10% Salt 7 1/2# Gilsonite per sack 3/4 of 1% FRA-2 PD @ 1:15 p.m. 11-29-81</p>

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 9th day of December, 1981.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

5111
 0111