

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

2-8  
API NUMBER 15-077-20944-00-00

LEASE NAME Ferrell #6

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NW NW

SEC. 19 TWP. 32 S RGE. 8 W (E) or (W)

COUNTY Harper County

Date Well Completed \_\_\_\_\_

Plugging Commenced 2/4/85

Plugging Completed 2/8/85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kelso Casing bought f/ Resource Venture Corp.

ADDRESS 1501 Superior, Lincoln, Neb. 68521

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3795'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8  | 270'   | none       |
|           |         |      |    | 4 1/2" | 3793'  | 2878'      |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 35 sacks cement 3% c.c. & plug to 3500'. Shot pipe at 3100', 3020', and 2878'. Pulled 34 joints. Pumped 50 sacks gel @ 1500', pulled pipe to 300', pumped 125 sacks 50/50 poz 2% gel 3% c.c. Pulled rest of pipe. (70 joints total).

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

FEB 12 1985

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1985



Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_