

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-07720692-00-00

LEASE NAME Calvert

WELL NUMBER 1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 19 TWP. 32 RGE. 8 (E) or (W)

COUNTY Harper

Date Well Completed 6-23-81

Plugging Commenced 11-24-00

Plugging Completed 11-28-00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R & B Oil & Gas, Inc.

ADDRESS PO Box 195 Attica, KS 67009

PHONE#(316) 254-7251 OPERATORS LICENSE NO. 31191

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-22-00 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? NO If not, is well log attached? _____

Producing Formation Stal Depth to Top 3670 Bottom 3800 T.D. 3803

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Stal</u>	<u>Gas</u>					
				<u>8 5/8</u>	<u>286</u>	<u>0</u>
				<u>4 1/2</u>	<u>3803'</u>	<u>2842'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom. Bailed 4 sacks of Portland. Shot at 3068'. Worked pipe, no gain. Shot 2842'. Pulled to 1200'. Pumped 35 sacks. Pulled to 650'. Pumped 35 sacks. Pulled to 300'. Circulated cement to surface. Hole stayed full.

Name of Plugging Contractor Quality Well Service License No. 99925

Address 415 E. Main St., Sterling, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.

STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above described well as filed the the same are true and correct, so help me God.

(Signature) Randy Newberry

(Address) PO Box 195 Attica KS 67009

SUBSCRIBED AND SWORN TO before me this 19th day of December, 192000

Rebecca S. Newberry
Notary Public

My Commission Expires: 7-21-2001

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 22 2000
CONSERVATION DIVISION
WICHITA, KS

REBECCA S. NEWBERRY
NOTARY PUBLIC
12-21-2001