

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER ¹⁵ 077-20,902-00-00

LEASE NAME Attica City

WELL NUMBER #3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

175 Ft. from S Section Line

650 Ft. from E Section Line

LEASE OPERATOR Attica Gas Venture Corp.

SEC. 19 TWP. 32 RGE. 8 (●) or (○)

ADDRESS 123 N. Main Attica, KS 67009

COUNTY Harper

PHONE# (316) 254-7222 OPERATORS LICENS. NO. 5039

Date Well Completed 9-8-83

Character of Well Gas

Plugging Commenced 10-30-91

(Oil, (Gas), D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-2-91

The plugging proposal was approved on 11-2-91 (date)

by Steve Van Gieson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Stalnaker Depth to Top 3678' Bottom 3702' T.D. 3850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
<u>Stalnaker Gas</u>	<u>3678' to 3702'</u>	<u>Surface</u>	<u>57'</u>	<u>13 7/8"</u>	<u>57'</u>	<u>-0- NOV 14 1991</u>
		<u>Surface</u>	<u>312'</u>	<u>8 5/8"</u>	<u>312'</u>	<u>-0-</u>
		<u>Surface</u>	<u>3846'</u>	<u>5 1/2"</u>	<u>3846'</u>	<u>2617</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Set CIBPC @ 3628' - 2 sack on top w/ bailer. Mud from 3628' to 1407'. 30 sack from 1407' to 1287' - displaced w/ mud. Mud from 1287' to 907'. 30 sack from 907' to 787' - displaced w/ mud. Mud from 787' to 366'. Cement from 366' to surface. Used 175 sack Class "A" Cement + 2% GACL

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AGVC - John Eck

STATE OF Kansas COUNTY OF Sumner, ss.

Carl W. Durr (Employee of Operator) _____ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) RR #1 Box 16A-3 Milton, KS

SUBSCRIBED AND SWORN TO before me this 12th day of NOVEMBER, 1991



Wendy S. Rorabaugh
Notary Public

My Commission Expires: 4-19-92