

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 077-20,744-00-00

LEASE NAME Attica City

WELL NUMBER #2

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 19 TWP. 32 RGE. 8 (N) or (W)

COUNTY Harper

Date Well Completed 11-26-81

Plugging Commenced 11-4-91

Plugging Completed 11-5-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Attica Gas Venture Corp.

ADDRESS 123 N. Main Attica, KS 67009

PHONE# (316) 254-7222 OPERATORS LICENSE NO. 5039

Character of Well Gas

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-5-91 (date)

by Steve Van Gisson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Stalnaker Depth to Top 3684' Bottom 3727' T.D. 3727'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
Stalnaker Gas/Water	3684' to 3727'	Surface	290'	8 5/8"	290'	-0-
		Surface	3684'	5 1/2"	3684'	2200'

NOV 14 1991

WICHITA DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Set CIRP @ 3634' - 2 sack on top w/ boiler. Water from 3634' to 1397'. 30 sack from 1397' to 1277'. Water to 915'. 30 sack from 915' to 795'. Water to 352'. Cement from 352' to surface. Used 205 sack Class "A" Common + 2% Cacl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AGUC - John Eck


STATE OF Kansas COUNTY OF Sumner, ss.

Carl W. Durr

(Employee of Operator) _____ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carl W. Durr

(Address) RR#1 Box 16A-3 Milton KS



SWORN TO before me this 12th day of NOVEMBER, 19 91

Wendy S. Rorabaugh
Notary Public

My Commission Expires: 4-19-92