

API NUMBER Comp. 2-3-56

LEASE NAME Dora Miller

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 2 TWP. 31S RGE. 9 (E) or (W)

COUNTY Harper

Date Well Completed 2-3-56

Plugging Commenced 1-17-95

Plugging Completed 2-7-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?         

Producing Formation Mississippian Depth to Top 4461 Bottom 4465 T.D. 4530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	240'	8-5/8"	240'	None
		0	4510'	5-1/2"	4510'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set  
Plugged and abandon using 60/40 Pozmix, 4% geland 2%cc. Set CIBP @ 950'. Perforated casing @ 900'. Perforated @ 800'. Pumped 35 sks cement. Displaced plug and cement to 600'. Set CIBP @ 250'. Perforate casing @ 240'. Pumped 90 sks cement and circulated cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address P. O. Box 781624, Wichita, KS 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) John Coyne

(Address) 3017 N. Cypress  
Wichita, KS 67226



before me this 17th day of March, 19 95

Deborah Ann Paulus  
Notary Public

January 8, 1996