

API NUMBER 15-135-23,871-0000

LEASE NAME Smith "VV"

WELL NUMBER 1

660' Ft. from X Section Line

410' Ft. from E Section Line

SEC. 9 TWP. 16S RGE. 23 (E) or (W)

COUNTY Ness

Date Well Completed 4-13-95

Plugging Commenced 4-13-95

Plugging Completed 4-13-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Co. Inc.

ADDRESS 110 N. Market, Suite 205 - Wichita, Kansas 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-13-95 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom T.D. 4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing			8 5/8"	225'KB	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

P&A as follows: 50sx @ 1810', 80sx @ 1050', 40sx @ 250', 10sx @ 40', 15sx in rathole (total 195sx of 60-40 poz, 6% gel w/1/4# Floseal per sx. Complete @ 6:15 AM on 4-13-95.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Company Tools License No. 5123

Address 110 N. Market, Suite 205 - Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


C.W. Sebitts, President of Pickrell Drilling Company, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) C. W. Sebitts, President
110 N. Market, Suite 205

Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 95



My Commission Expires: 6-06-98

Verdella Lewis

Notary Public

APR 25 1995

4-25-95

STATE CORPORATION COMMISSION
WICHITA, KANSAS

EFFECTIVE DATE: 4-2-95
DISTRICT # 1
SGA? Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL

135-23,871-~~0000~~ 2
FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Expected Spud Date 4 - 7 - 1995
month day year

Spot 80' W of E/2
NE NE Sec 9 Twp 16S, Rg 23 East West

OPERATOR: License # 5123
Name: Pickrell Drilling Company, Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas 67202
Contact Person: Don W. Beauchamp
Phone: 316-262-8427

660 feet from South / North line of Section
660-470 feet from East / West line of Section

IS SECTION X REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5123
Name: Company Tools

County: Ness
Lease Name: Smith "VV" Well #: 1
Field Name: Wildcat

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Mississippian

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWMO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

Nearest lease or unit boundary: 660-470
Ground Surface Elevation: 2380 Feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

If OWMO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Depth to bottom of fresh water: 96 150
Depth to bottom of usable water: 904 1030

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 225'

Length of Conductor pipe required: None
Projected Total Depth: 4425'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

DWR Permit #: _____
Will Cores Be Taken? yes X no
If yes, proposed zone: _____

Exp. 9/28/95

AFFIDAVIT

200' Alt. II Req. **RECEIVED**
KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met: **MAR 28 1995**

Pusher Dwyler
SPUD DATE 4.6.1995 INIT. GB
LENGTH SURFACE PLANNED 225
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 225 CONDUCTOR
ANHYDRITE T- 1221 B- 1811 ELEVATION
TD 450 FORMATION MCS
RAN PIPE @ SX DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hng./Council @ Ft. W/ SX
Anhydrite Base @ 1810 Ft. W/ 54 SX
1/2 Base Anhy. @ 1050 Ft. W/ 80 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 250 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond)
Hauling
TECHNICIAN R.L.P. DATE 4-11-95
TYPE OF CEMENT 60/140 p.c. 6' bagel 1/4 Flashed
STARTING TIME 4:00 (AM/PM) DATE 4-13-95
COMPLETION TIME 4:55 (AM/PM) DATE 4-13-95
CEMENT COMPANY 2010