

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15.135.21460.0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 9 Twp. 16S Rge. 23W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW SE


Lease Owner Beren Corporation
Lease Name Farr Well No. #1
Office Address 970 Fourth Financial Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed June 27, 1978 19
Application for plugging filed June 27, 1978 19
Application for plugging approved June 27, 1978 19
Plugging commenced June 27, 1978 19
Plugging completed June 27, 1978 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4480'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Completed 3:15 p.m. June 27, 1978.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.
Kenneth J. Link (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Kenneth J. Link President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1978.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80.

RECEIVED
STATE CORPORATION COMMISSION



JUL 18 1978
7-18-78
CONSERVATION DIVISION
Wichita, Kansas

15-101-21460-0000

D R I L L E R S L O G

#1 Farr

CASING RECORD: 333.41' used 8-5/8" surface casing	COMPANY: Beren Corporation	DESCRIPTION: NW SE Section 9-16S-23W Ness County, Kansas
TOTAL ROTARY DEPTH: 4480'	CONTRACTOR: Strata Drilling Company	
	COMMENCED: June 20, 1978	
	COMPLETED: June 27, 1978	

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale and sand	0	345	Ran 8 jts. used 8-5/8" surface casing, set and cemented @ 339' with 200 sacks 60-40 pozmix, 2% gel, 3% C.C. Cement circulated. Plug down 11:59 p.m., June 20, 1978.
Shale and sand	345	1200	
Shale	1200	1787	
Anhydrite	1787	1826	
Shale	1826	2460	
Lime and shale	2460	4480	

Ran 2 drill stem tests.

Ran 1 electric log.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 720', 20 sacks @ 240', hulls and 10 sacks @ 40'. Completed 3:15 p.m., June 27, 1978.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1978

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Sworn to and subscribed before me this 30th day of June, 1978.

My commission expires 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

