

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Tuthill & Barbee Inc. 15:135:22199-675023
Address 300 Fisk Building, Amarillo, Texas 79101
Lease (Farm Name) Hays Well No. 1-17
Well Location SE SE Sec. 17 Twp. 16S Rge 23W (E) (W)
County Ness Total Depth 4602' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log filed with application as required Yes
Date and hour plugging is desired to begin February 6, 1982

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Dowell Address Great Bend, Kansas

Plugging Contractor Dowell License No.

Address Kansas

Invoice covering assessment for plugging this well should be sent to:

Name Tuthill & Barbee, Inc.

Address 300 Fisk Building, Amarillo, Texas

and payment will be guaranteed by applicant or acting agent.

Signed: John R. Bartholomew
Applicant or Acting Agent

Date: February 10, 1982

*Recd
2-22-82*


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-135-22199-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 17 Twp. 16S Rge. 23W E/W
Location as "NE/CNW/SW" or footage from lines
SE SE
Lease Owner Tuthill & Barbee
Lease Name Hays Well No. 1-17
Office Address 300 Fisk Building, Amarillo, Texas
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed February 6 1982
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 6 1982
Plugging completed February 6, 1982 19
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dowell
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4602'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	821	8-5/8"	821	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

1st plug @ 1020' w/70 sax Class H, 2nd plug @ 420 w/40 sax
Class H, 3rd plug @ 40' w/10 sax Class H, 5sax in rat hole & 5 sax
in mouse hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell

STATE OF Kansas COUNTY OF Sedgwick, ss.

John R. Bartholomew (Signature)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew

(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of February, 1982

Louise K. Whitted
Notary Public.



My commission expires

RECEIVED
STATE CORPORATION COMMISSION
3-1-82
MAR 1 1982

CONSERVATION DIVISION
Wichita, Kansas

15135-22199-0000

DRILLERS LOG

HAYS NO. 1-17

CASING RECORD:	OPERATOR:	Tuthill & Barbee	DESCRIPTION:
8-5/8" set @ 821' w/425 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	SE SE Sec. 17-16S-23W Ness County, Kansas
TOTAL DEPTH: 4602'	COMMENCED:	January 30, 1982	
	COMPLETED:	February 6, 1982	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	1273	
Red Bed & Anhydrite	1273	2546	
Shale & Sand	2546	2693	
Shale	2693	3880	
Lime & Shale	3880	4004	
Shale	4004	4256	
Lime	4256	4602	Logged Hole, Ran DST #1 " DST #2 " DST #3 D & A

I certify that this is a true and correct copy of the logs on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

BY John R. Bartholomew
John R. Bartholomew

Subscribed and sworn to before me this 16th day of February, 1982.

Louise K. Whitted
Louise K. Whitted, Notary Public

