

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # Comp. 02-03-56 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/95

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS 3017 N. Cypress CITY Wichita

STATE Kansas ZIP CODE 67226-4003 CONTACT PHONE # (316) 636-2737

LEASE Dora Miller WELL# 1 SEC. 2 T. 31S R. 9W (~~East~~ West)

SW - SW - SW - SPOT LOCATION/QQQQ COUNTY Harper

_____ FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

_____ FEET (in exact footage) FROM (E) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 240' CEMENTED WITH _____ SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4510' CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs @ 4461-4465'

ELEVATION _____ T.D. 4530' PSTD _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Dump sand to 4400' & cap with 5 sx cement. Shoot & pull casing according to stretch. Pull casing to 1350' & spot 35 sx cement. Pull casing to 900' & spot 35 sx cement. Pull casing to 300' & circulate cement to surface. Pull remaining casing & top off cement. 60/40 Poz 4% Gel. Orders by Steve VanGieson w/ KCC.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl J. Hanson PHONE# (316) 272-1296

ADDRESS P. O. Box 2250 City/State Garden City, KS 67846

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE # 30346
(company name) (contractor's)

ADDRESS P. O. Box 781624 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) _____

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11-17-94 AUTHORIZED OPERATOR/AGENT: _____

(signature)

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1994
WICHITA, KANSAS



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

November 21, 1994

McCoy Petroleum Corporation
3017 N Cypress
Wichita KS 67226-4003

Dora Miller #1
API 15-N/A
SW SW SW
Sec. 02-31S-09W
Harper County

Dear Daryl J. Hanson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #2
202 W. First, Suite 304
Wichita KS 67202
(316) 263-8809