

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-23,438-0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR N.C.R.A. OPERATOR'S LICENSE NO. 5565

ADDRESS 1775 Sherman St., Suite 801
Denver, CO 80203 PHONE # (303) 861-4883

LEASE (FARM) Mishler WELL NO. 1 WELL LOCATION SW NW COUNTY Ness

SEC. 29 TWP. 16S RGE. 23 ~~(E) (W)~~ TOTAL DEPTH 4600' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 357.09' CEMENTED WITH 235 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 1890'-50 sx. 2nd
plug at 915'-80' sx. 3rd plug at 390'-40 sx. 4th plug at 40'-10 sx. Rathole-15 sx. All
cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1:15 a.m. on 03-23-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Anthony Martin PHONE # (913) 743-5443

ADDRESS 533 N. Main, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF WELL PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

APR 30 1990
4-30-90
UG-10-1000

SIGNED: Jack R. Wharton
(Operator or Agent)

DATE: 04-26-90