

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC - 7 1978
12-7-78

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,535-0000 (of this well)

Operator's Full Name Beren Corp.

Complete Address 970 4th Financial Center, Wichita, Kansas

Lease Name Baer Well No. 2

Location C SW SE Sec. 16 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 9 A Day 6 Month 12 Year 1978

The above well was plugged as follows:

RTD 4500' 8 5/8 csg set 334' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 810' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-11-78
87710.00

Signed: Leo Masny
Well Plugging Supervisor