

15135-20287-0000

Form CP-3

Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 3 1972

10-3-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Lindsay Pipe & Supply

Complete Address Box 487 Chase, Kansas 67524

Lease Name Baer Well No. 1

Location SE SW Sec. 16 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4445'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 3:15 P Day 2 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 4445' 8 5/8 csg set at 260' cwc Cmt. Mat. 50-50 poz cmt W/6% gel.

4 1/2 csg set at 4443' cw 125 sk cmt.

Filled 4 1/2 csg W/sd (4425-4445) Dumped 4 sk cmt W/dump bailer.

Cutoff and recovered 3100' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls, -70 sk cmt, -10 sk

gel & water, -released 8 5/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 10/3/72
INV. NO. 6416-u