

15-007-30277-00-00

Form CP-3
Rev. 6-26-62

J
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1966
11-14-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tom-Kat, Inc.

Complete Address: 1127 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Thom Well No. # 1

Location C SW NE Sec. 27 Twp. 30 Rge. 11 (E) (W)

County Barber Total Depth 3789'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Tom-Kat Drilling, Inc.

Address: 1127 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 10:00PM Day 12th Month Nov. Year 1966

The Above well was plugged as follows:

258' of 8 5/8" surface pipe, cement circulated with 210 sacks. Hole
was filled with drilling mud to 250', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 250', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/15/66

INV. NO. 4298-W

Signed: Archie Elving
Well Plugging Supervisor