

15735-30222-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 9 1966  
8-9-66  
WICHITA, KANSAS

Operator's Full Name Vaughn Drilling Inc.,

Complete Address: 1618 Wichita Plaza Wichita, Kansas

Lease Name Hindergardt Well No. 1

Location C NW NW Sec. 1 Twp. 16 Rge. 23 (E) (W) X

County Ness Total Depth 4360

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 11:30 A Day 6 Month 8 Year 1966

The Above well was plugged as follows:

RTD 4360 8 5/8 set at 241 cwc

Gunned pits, Circulated heavy mud, set cementing plug at 600 Ft. and displaced  
25 sc cement thru drill pipe. Heavy mud to 235 Ft. set cementing plug and displaced  
20 sc cement thru drill pipe Heavy mud to 40 Ft. set cementing plug, 1/3 sc hulls  
and 10 sc cement to base of celler. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 8/9/66  
INV. NO. 3420-W