

15-135-30147-0000

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

1-2-68
JAN 2 1968

Operator's Full Name Cities Service Oil Company

Complete Address Box 308 Great Bend, Kansas

Lease Name Kraus "A" Well No. 1

Location App. C S/2 NE NW Sec. 21 Twp. 16 Rge. 23 (E) (W) X

County Ness Total Depth 4476

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11:30 A Day 29 Month 12 Year 1967

The above well was plugged as follows:

Total Depth 4476' 8 5/8 csg set at 370' cwc 200 sc

4 1/2 csg set at 4475' cw 100 sc cement.

PBTD 4454' and perf 4449-54

Filled with sand to 4425 and dumped 4 sc cement with dump bailer.

Recov. 2241' of 4 1/2 csg.

Pumped thru 8 5/8 plg container with 20 sc gel-120 sc cement-10 sc gel-Plg and 15 sc cement and shutin. Pres 200 lbs.

Cement (0-50) gel (50-450) cement (450-800) gel 800 to TD.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Muesey
Well Plugging Supervisor

DATE 1-2-68

INV. NO. 7020-W