

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 21,534-6000 (of this well)

Operator's Full Name Beren Corp.

Complete Address 970 4th Financial Center, Wichita, Kansas

Lease Name Baer Well No. 1

Location C NW SE Sec. 21 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4550'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 6:30 P Day 28 Month 11 Year 1978

The above well was plugged as follows:

RTD 4550' 8 5/8 csg set 332' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 810' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1978  
11-30-78

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 11-30-78  
INV. NO. 8644-w