

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Inc.

Complete Address: 370 W Wichita Ave. Russell Kansas

Lease Name Schoppel Well No. 1

Location C SE SW Sec. 18 Twp. 16 Rge. 23W (E) (W) X

County Ness Total Depth 4544

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12:30 P Day 17 Month 7 Year 1968

The Above well was plugged as follows:

RTD 4544' 8 5/8 csg set at 264' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Mearns
Well Plugging Supervisor

DATE 7/19/68
INW. NO. 8144-U