

15135-30797-0000
Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
APR 21 1966
4-21-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer Inc.

Complete Address: 370 Wichita Russell, Kansas

Lease Name Schreiber Well No. 1

Location NE-SW Sec. 22 Twp. 16 Rge. 23 (E) (W) X

County Ness Total Depth 4570

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C.O. Tools

Address: License No.

Operation Completed: Hour 4 P Day 19 Month 4 Year 1966

The Above well was plugged as follows:

Total Depth 4570 5 B set at 251' cw 150 lbs. Cem. Circ.
Gunned pits circulated hole with heavy mud, set cementing plug at 500 ft.
and displaced 20 sac cement thru drill pipe, heavy mud to 250 ft., set
cementing plug and displaced 20 sac cement thru drill pipe, heavy mud to 40 ft.,
set cementing plug, 1 sac hulls and 10 sac cement., cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/21/66

INV. NO. 3083-W

Signed: L. J. Massey
Well Plugging Supervisor