

15135-20955-0000



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1974
10-21-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Icer Addis
Complete Address Drawer 8038, Wichita, Kansas
Lease Name Scherzinger Well No. 1
Location C NW NW Sec. 22 Twp. 16 Rge. (E) (W) 23
County Ness Total Depth 4465'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Strata Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 9:30 P Day 18 Month 10 Year 1974

The above well was plugged as follows:

RTD 4465' 8 5/8 csg set at 285' cwc 175 sx. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, displaced 70 sk cmt plug at 825' thru drill pipe.
Heavy mud to 300' & displaced 20 sk cmt plug thru drill pipe. Heavy mud to 40' ~~XXX~~
solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/23/74
INV. NO. 166-W

Signed: Paul J. Massey
Well Plugging Supervisor