



15-077-30006 or 00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1965
06-14-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Shipley of Graybol Oil Corporation has this date requested permission to plug the following described well:

Mr. Shipley guarantees payment of the plugging fee.

Operator's full Name: Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Okla.

Lease Name: Elmore Well No. # 1

Location: C SE NE Sec. 5 Twp. 31 Rge. 7 (E) (W) W

County Harper Total Depth 4777' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shipley was instructed to plug the well as follows:

219' of 8 5/8" surface pipe, cement circulated with 175 sacks.

Fill hole with drilling mud to 210', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with

2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent