

R

Form CP-3

KANSAS

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
Rev. 6-4-68

CONSERVATION DIVISION AGENT'S REPORT

MAY 09 1977
5-9-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,306-0000 (of this well)

Operator's Full Name Chief Drilling Co., Inc.

Complete Address 905 Century Plaza, Wichita, Kansas

Lease Name Dietterich Well No. 1

Location G S/2 NW/4 Sec. 33 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4525'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor Co. Tools

Address _____ License No. _____

Operation Completed: Hour 1:30 A Day 5 Month 5 Year 1977

The above well was plugged as follows:

RTD 4525' 8 5/8 csg set 285' cwc 180 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 5-9-77

INV. NO. 5111-47