

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,572-6060 (of this well)

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Ks.

Lease Name Schoeffel Well No. 1

Location C SW NE Sec. 31 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4528'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Pioneer Drlg.

Address Plainville, Ks. License No.

Operation Completed: Hour 5 P Day 18 Month 1 Year 1979

The above well was plugged as follows:

RTD 4528' 8 5/8 csg set 302' cwc 180 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 22 1979
1-22-79
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-22-79
INV. NO. 8989-W

Signed: Red Messerly
Well Plugging Supervisor