

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

4-26-77

API Number 15 - 135 - 21,315 - 0000 (of this well)

Operator's Full Name Walters Drilling Co.

Complete Address 400 Insurance Bldg., Wichita, Kansas

Lease Name Klitzke "B" Well No. 1

Location C SE SW Sec. 31 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4565'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Slawson Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:15 A Day 25 Month 4 Year 1977

The above well was plugged as follows:

RTD 4565' 8 5/8 csg set 307' cwc 200 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Les Massey
Well Plugging Supervisor

INVOICED
DATE 4-26-77
INV. NO. 5036-W