

STATE CORPORATION COMMISSION

15-135-20642-6000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1972
7-11-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Patrick Petroleum

Complete Address Suite 330 Page Court, 220 W. Douglas Wichita, Kansas

Lease Name Horchem Well No. 1

Location NW NW Sec. 31 Twp. 16 Rge. (E) (W) 23

County Ness Total Depth 4578'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil

Address Wichita, Kansas License No.

Operation Completed: Hour 5:15 A Day 8 Month 7 Year 1972

The above well was plugged as follows:

RTD 4578' 8 5/8 csg set at 324' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Marshall
Well Plugging Supervisor

INVOICED

DATE 7/11/72

INV. NO. 6014-W