

KANSAS

STATE CORPORATION COMMISSION

15-135-20228-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-13-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name William H. Pine  
Complete Address McCulloch Bldg., Okmulgee, Oklahoma 74447  
Lease Name Harkness Well No. 1  
Location C NE SE Sec. 11 Twp. 20 Rge. (E) (W) 25  
County Ness Total Depth 4472  
Abandoned Oil Well XXX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Forbes Casing Pulling Co.  
Address Box 221 Great Bend, Kansas License No. 637  
Operation Completed: Hour 10:30 A Day 6 Month 11 Year 1970

The above well was plugged as follows:

Total Depth 4472' 8 5/8 csg set at 241' cwc 145 sk.  
4 1/2 csg set at 4463' cw 75 sk cmt.  
4 1/2 csg PBTD 4465 1/2' with top perf. (4462)  
DV tool set at 1582' cw 675 sk cmt.  
Filled 4 1/2 csg W/sd (4450-4465 1/2) Dumped 4 sk cmt W/dump bailer. (4415-4450)  
Set wood plug (4 1/2) at 600' poured 10' sd and dumped 2 sk cmt W/dump bailer. (575-600)  
Shotoff and recovered 450' of 4 1/2 csg.  
Filled 8 5/8 csg with readymix cmt. (0-240)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les F. Murray  
Well Plugging Supervisor

DATE 11-13-70  
INV. NO. 2849-U