

15-135-304046000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 1969
CONSERVATION DIVISION
Wichita, Kansas
10-3-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Wm H. Pine

Complete Address: McGulloch Bldg., Okmulgee, Oklahoma 74447

Lease Name Stick Well No. 1

Location C SW SW Sec. 12 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4458'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 2:30P Day 1 Month 10 Year 1969

The Above well was plugged as follows:

Total Depth 4458' 8 5/8 csg set at 476' cwc

4 1/2 csg set at 4457' cw 250 sk cmt.

4 1/2 csg perf. (4447-4457)

Tubing packer stuck at 4308' with top of tubing at 3700'.

4 1/2 csg squeezed at 795' W/400 sk cmt and circulated to surface. No pipe recovered.

Ran 2 1/2 tubing to 3670' - circulated 20 sk gel & water to surface. Displaced 20 sk cmt

(3470-3670). Pulled tubing to 750', circulated 80 sk cmt (0-750)

Checked amilus (4 1/2 - 8 5/8) 500 lbs. pres.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/3/69
INV. NO. 585-W

Signed: [Signature]
Well Plugging Supervisor