

15:35-20516-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*4* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
11-29-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Schlegel Well No. 1

Location 660' FNL & 990' FEL <sup>*C W/2 NE NE*</sup> Sec. 14 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4490'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 1:30 A Day 25 Month 11 Year 1971

The above well was plugged as follows:

RTD 4490' 8 5/8 csg set at 550' cwc Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 420' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 12/1/71

INV. NO. 4754-W