

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1972
11-27-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas 67202

Lease Name Gibson Well No. 1

Location C SW SW Sec. 17 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4489'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2 P Day 24 Month 11 Year 1972

The above well was plugged as follows:

Total Depth 4489' 8 5/8 csg set at 564' cwc 325 sk.

5 1/2 csg set at 4477 1/2' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (4450-4489) dumped 5 sk cmt W/dump bailer. (4415-4450)

Cutoff and recovered 2600' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

and pumped 50 sk cmt -displaced with 10 sk gel & water -and capped with 20 sk cmt.

Cementing by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Pat F. Murray
Well Plugging Supervisor

INVOICED
DATE 11/29/72
INV. NO. 6692-W