

9

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

15-135-20495-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

OCT 12 1971

CONSERVATION DIVISION  
Wichita, Kansas

10-12-71

Operator's Full Name Murfin Drilling Company  
Complete Address 617 Union Center Wichita, Kansas  
Lease Name Gibson Well No. 2  
Location 150' So. of C NW SW Sec. 17 Twp. 20 Rge. (E) (W) 25  
County Ness Total Depth 4509'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 5:30 P Day 8 Month 10 Year 1971

The above well was plugged as follows:

RTD 4509' 8 5/8 csg set at 560' cwc: 300 sk Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 400' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing  
Well Plugging Supervisor

DATE 10-13-71  
INV. NO. 4464-W