

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 125-22, 015 ^V -0000

Operator's Full Name DONALD C SLAWSON

Complete Address 200 DOUGLAS BLDG., WICHITA, KANS.

Lease Name MLEIN Well No. 'E' #1

Location NE-SW-SE Sec. 23 Twp. 20 Rge. 25 (East) (West)

County NESS Total Depth 4530 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor SLAWSON DRILLING, INC.

Address 200 DOUGLAS BLDG, WICHITA, MO. License No. _____

Operation Completed: Hour: 3:00 PM Day: 29th Month: APRIL Year: 19 81

The above well was plugged as follows:

8 5/8" 518 FE SP. CULC w/ 275 # 60/40 PORMIX - 2% GEL. - 23% CH-CL.

ORDERED 110 # 50/100 PORMIX 6% GEL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG. @ 860 FE w/ 65 # CMT.

2ND PLUG. @ 540 FE w/ 30 # CMT.

3RD PLUG. -> SOLID BRIDGE @ 40 FE/0 w/ 10 # CMT.

5 # IN RAT HOLE.

CEMENTED BY WALLISERON CMT.

5-1-81

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-29-81

5584-W

Signed: Walter J. Smith
Conservation Division Agent