

15-135-20337-0000

Form CP-3  
Rev. 6-4-68

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 672025-11-70  
RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Strata Drilling, Inc.

Complete Address P. O. Box 355 Great Bend, Kansas 67530

Lease Name Roth Well No. 1

Location C SE SE Sec. 20 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4480

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 8:45P Day 6 Month 5 Year 1970

The above well was plugged as follows:

RTD 4480' 8 5/8 csg set at 289' cwc 160 sk. Cmt. Mat. 50-50 poz cmt. W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

5/11/70

INV. NO.

1869-41

Signed:

Well Plugging Supervisor

Leo Z. Maxey