

15-135-20509-0000

Form CP-3
Rev. 6-4-68

KANSAS

of
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1971
CONSERVATION DIVISION
Wichita, Kansas
11-15-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Strata Drilling, Inc.
Complete Address Box 355 Great Bend, Kansas
Lease Name McVickers Well No. 1
Location C NE NE Sec. 19 Twp. 20 Rge. (E) (W) 25
County Ness Total Depth 4490'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 6:25 P Day 14 Month 11 Year 1971

The above well was plugged as follows:

RTD 4490' 8 5/8 csg set at 288' cwc 160 sk. Cmt. Mat. 50-50 poz W/6% total Gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Marney
Well Plugging Supervisor

DATE 11-15-71
INV. NO. 4655-W