

KANSAS  
STATE CORPORATION COMMISSION R

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

FEB 7 1966

2-7-66

CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Tom-Kat, Inc.

Complete Address: 1127 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Schiff Well No. # 1

Location NE SW NW Sec. 11 Twp. 32 Rge. 11 (E) W

County Barber Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Tom-Kat Drilling, Inc.

Address: 1127 Wichita Plaza Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 6:00 PM Day 5th Month Feb. Year 1966

The Above well was plugged as follows:

240' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole  
was filled with drilling mud to 240', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 240', and cemented with 25 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridged and cemented with  
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2-8-66

INV. NO. 2690-W